



THE CEILING SPACE THROUGHOUT THIS PROJECT IS A RETURN AIR PLENUM. NO COMBUSTIBLE OR TOXIC MATERIALS ARE ALLOWED ABOVE THE CEILING.

HVAC PROJECT SPECIFIC NOTES
 CONTRACTOR IS TO INSPECT ALL EXISTING DUCTWORK SHOWN ON THESE PLANS AS REMAINING. REPAIR AS REQUIRED ANY DAMAGED DUCTWORK OR INSULATION. WHERE DUCTWORK IS SHOWN TO BE PARTIALLY REMOVED, CAP, SEAL, AND INSULATE TO MATCH EXISTING METHODS AND MATERIALS. EXISTING VAV UNITS WHICH ARE REMAINING ARE TO BE INSPECTED, ADJUSTED AND REPAIRED WHERE NECESSARY.

EQUIPMENT TO BE MODIFIED IS SHOWN IN BOLD ON THIS PLAN (TYPICAL)

HVAC 4TH FLOOR PLAN - EXISTING
 SCALE: 1/8" = 1'-0"

Gilman & Associates, Inc.
 MECHANICAL & ELECTRICAL ENGINEERS
 507 NORTH LAKESIDE DRIVE
 Lake Worth, FL 33460 C.A.#009078
 (561) 582-0210 Fax (561) 582-8212
 RONALD D. GILMAN P.E. #37933

BD

birse design inc.

5300 woodland lakes drive
 palm beach gardens, fl 33418
 phone 561-249-4001
 fax 772-409-8884
 AA26001615

ANTHEM

FAIRWAY OFFICE CENTER
 7111 FAIRWAY DR #402
 PALM BEACH GARDENS, FL

PROJECT NUMBER 711112

REVISIONS

1	
2	
3	
4	
5	

DRAWN BY DR

CD

3-14-12

